



LAB NAME HERE

123 Main Street, PA 12345

Phone: 888-555-1212



Brick Flexural Center-Point Test

Project Number	HARMONY P	Machine	F-250-VFD-D
Location Name	83457	Calibration Date	07/17/2024
Sample Number	2410046	Technician	EB
Set Number	116	Sample Date	10/28/2024 12:00

Specimen Data

Specimen Number	1	Weight	19.1 lb
Span Length	7 in		
Width Avg	8.94 in		
Thickness Avg	2.74 in		
Length Avg	8.95 in		

Results Data

Test Date	10/28/2024 12:49	MOR	870 psi
Preload	200 lbf	Break Type	0
Ramp Rate	1291.82 psi/min	Break Width	-
Max Load	5,560 lbf	Break Depth	-
Max Stress	870 psi	End Cond	
		End Value	

https://forneytools.forneyvault.com/Report/95cc674e-85f6-4d36-83f8-2f3a432e001e

